



SWAN GREEN BUS SHELTER (3) - groundworks



SPC has approved installation of a wooden bus shelter, more in keeping with the locality, to replace the dilapidated metal one. Assuming all applications are approved work should begin in April and take about one week.

Contractor	Specification	Cost
The Shed Man Chiddingstone, Kent Andy Baker 01892 870006 07785 745213 wwwtheshedman.info	"Village Rural Bus shelter" excluding the base. Designed to be in keeping in the countryside, low maintenance, visibility, long life span, and to protect and withstand all weathers. Dimensions: Shelter size; 2.48m x 0.73m Roof size; 3.1m x 1.6m	Supply and installation: £4,150.00 Delivery: £250.00 Deposit paid and contractor ready to deliver as soon as permission received from EH.
CS Mason Michael Billam	Sub base – 100mm Type 1 Basecourse – 40mm Dense Bituminous Macadam Wearing Course – 20mm Dense Bituminous Macadam Edging around the hard standing can be wooden or concrete.	Traffic Management: £695.85 Works: £4,129.65 Total: £4,825.50
COLNE CONTRACTS LIMITED A.J. Walther	To excavate the area 210 mm depth and cart away spoil. To lay MOT Type 1 sub base 50 mm thickness to the excavated area. To install a pre-coated	Works: £2,180.00 Incl. 2-way traffic management



Stanway

Parish Council

	timber edging to the exposed edges. To lay concrete 100 mm thickness to the Type 1 sub base. To lay dense bitumen macadam 60 mm thickness to the concrete base.	
--	---	--

I have approached seven other contractors but have been unsuccessful in getting another quotation.

Other considerations:

1. Application A for works to be made to Essex Highways - permission granted.
2. Application 20 to Essex Highways to install a new bus shelter – permission granted.
3. Removal of bus stop sign and have signs attached to bus shelter – permission granted.
4. Placement of planters each side of bus stop to enhance rural setting. (Application to be made to Essex Highways and costs to be investigated)
5. To take over responsibility of litter bin at bus stop.
6. Kessel Curb (grants available and contact made)
7. Traffic control – costs included by contractors). Traffic management company confirmed that the works will need to have a 2 way traffic system whilst the works go on.